

Old World Masonry Construction, Inc

2820 San Jacinto Circle
Sanford, FL 32771

Estimate

Date	Estimate No.
2/26/2021	474

Name/Address

Palm Lake HOA
8716 Crestgate Circle
Orlando, FL 32819
pallakehomeownersassoc@gmail.com

*The Bitterness of Poor Quality Lingers Long
After the Cheap Price is Forgotten*

Project

Description	Qty	Rate	Total
West side fountain regrout	1	750.00	750.00
Repair of 600' x 7' wall on west side: chisel out loose mortar, remove rusting metal lathe, regrout using matching colored mortar	1	9,000.00	9,000.00
1450ft of tuck pointing buff mortar into openings scattered though back of south wall (sight unseen)		7,700.00	7,700.00
Repair of 1440' x6' wall on north side: fill open mortar joints as needed	1	2,000.00	2,000.00
Repair broken column and fill hole at home 8741 West Side TBD	1	850.00 0.00	850.00 0.00
Total			\$20,300.00

* 50% nonrefundable deposit required
* Draws on completed construction due 5 days after invoicing

- A. Owner shall supply water, survey and land will be at owner's desirable grade and site will be accessible for workers and equipment.
- B. Old World Masonry shall supply all labor and tools necessary to complete masonry work and haul away debris
- C. Construction will be field measured for accuracy upon completion, this may result in a price change
- D. Price good for 30 days from estimate date.
- E. This price does not include paint, pumping, tile; capping or landscaping.
- G. Permit and engineering costs (if needed)will be added.

Signature _____